BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2022-23/OW/WORK_INDENT54278

APPROVED SCHEDULE - B

No.EE/BTP/BBMP/E-PMT/18/2022-23, Dated: 04-11-2022.

Name of Work: Improvements to roads and drains in ward no 12 - Kodigehalli.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of SHARATH J N (SRI CHOWDESHWARI CONSTRUCTIONS)	
				In Figures	In Words
1	779.52	Removing and Resetting of Footpath Slab and pointing in C.M (1:3)	Sqm	200.0	Rupees Two Hundred Only
2	126.76	Earth work excavation by manual means for drains,canals, waste weir, draft, approach channels, key trenches, foundation of bridges and such simillar works in all kinds of soils , as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, removal of stumps and other deleterious matter, excavated surface leveled and sides neatly dressed disposing off the excavated stuff or sorting & stacking the selected stuff for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools & other appurtenaces required to complete the work	Cum	150.0	Rupees One Hundred Fifty Only
3	25.20	Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts and lead Prestressed / RCC grade M-20 & above.	Sqm	1100.0	Rupees One Thousand One Hundred Only
4	334.08	Providing and Fixing pre cast covering Slab made out of CC 1:2:4 with 10cm thick made of M25 with OPC cement @ 340kgs per Cum with 20 mm and Down size graded granite metal coarse agg @.70 mixed including providing and removing centering, shuttering, shuttering propping etc. for edges of slabs with TMT (Fe500) COM, labor, labor, all Lead and Lift, HOM, Curing, including Cost of reinf. Etc, Complete as directed by the Engineer In charge of Work	Sqm	1650.0	Rupees One Thousand Six Hundred Fifty Only
5	33.60	Providing and Fixing pre cast covering Slab 230mm thick made out of CC , Jelly 20mm Down Size with steel reinforcement including form work, curing, including cost of all materials, labour, hire charges of machinery, loading, unloading, lead and lift, transportation etc, complete as per Engineer incharge.	Sqm	4300.0	Rupees Four Thousand Three Hundred Only
6	589.88	Cost of Haulage Excluding Loading and Unloading Taking output 10 t load and lead 10 km = 100 t.km	t.km	105.0	Rupees One Hundred Five Only

Sharath

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92.

ಕಾರ್ಯ ಪಾಲಕ ಅಭಿಯಂತರರು
ಬ್ಯಾಲಕವಾಡಿಪುರ ವಿಭಾಗ
ಬೃ.ಬೆ.ಮ.ಪಾ., ಬೆಂಗಳೂರು